BANGALORE DIVISION.

Notification dated 23rd January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 1st February 1928, for constructing Urdu Middle School Building at Closepet. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Urdu Middle School Building" at Closepet, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract of quantities for the Urdu School, Closepet.

No.	Items of work	Quantity	Per unit	Rate
1	Earthwork excavation and filling basement	88	C.yds.	
2	Burnt stone jelly concrete in mortar	666	C.ft.	
3	Burnt stone in clay	1857	„	
4	Burnt brick in clay	2817	„	
4a	Burnt stone slabs 6" roughly dressed	370	S.ft.	
5	Burnt brick in mortar	570	C.ft.	
6	Segmental arch work as per deductions	118	„	
7	Teakwood panel doors with 1½" thick plank shutters with glazed ventilators at top, iron fittings, etc., complete.	140	S.ft.	
8	Teakwood panel windows 1" thick shutters with 1½" glazed ventilators at top, iron bars, iron fittings, etc.	175	„	
9	Teakwood expanded metal windows with Iron bars ...	68	„	
10	Teakwood work wrought and put up including wood oiling	145·42	C.ft.	
11	King Post Truss with iron fittings, etc., complete ...	1·75	„	
12	Roofing with 1st class Mangalore tiles on 2"×1" on teak reepers.	29·34	Sqr.	
13	Ridge tiles set in mortar	125	R.ft.	
14	Teakwood planks on zinc sheets for valley	252	S.ft.	
15	Teakwood eave board	323	R.ft.	
16	Teakwood finials	5	each	
17	Teakwood pendents	12	„	
18	Cement fillet for valley	84	R.ft.	
19	Cuddapah slab on 3" concrete bed and cement pointing ...	15·26	Sqr.	
20	Tarring to wood work	5·00	„	
21	Plastering with mortar	38·02	„	
22	Rough cast work with sand screenings and pebbles including plastering.	20·20	„	
23	Cement pointing to basement	3·59	„	
24	Stone pillars	80	R.ft.	
25	Whitewashing	38·00	Sqr.	
26	Cement washing	20·20	„	
27	Chocolate painting ..			
28	Barge board			